

PUMPED UP AND READY TO FLOW

BBA BV150 Electric driven

GENERAL INFORMATION

ID 23P00101

Make BBA

Type Electric driven

Year 2018

Operating hours 27

Construction Water pumps

Fuel Electric
Weight 1.640 kg

Power kw 30 Power hp 41

 Length
 267 cm

 Width
 104 cm

 Height
 140 cm





TECHNICAL INFORMATION

available with any desired quick coupling.
 Can be used immediately
 in stock!
 PUMPED UP AND READY TO
 FLOW!
 self-priming (dry)
 Spare parts available, usually in stock
 Stack frame
 Supported by van vacuum pump

DESCRIPTION

BBA BV-150 dry self-priming pump

This BV series pump is designed with an emphasis on reliability and durability. Thanks to its fully mechanical vacuum system, these pumps prime quickly, even without liquid in the pump housing. Due to its heavy construction, this pump from the BV series is ideal for use in vertical and horizontal drilling techniques.

World-class performance this pump from the BV series is used for the most demanding bentonite and sludge applications. A robust overall design ensures maximum performance of this pump.

This pump is equipped with a soft starter. This motor control ensures a smooth start with constant acceleration, lowers the inrush current and prevents unnecessary mechanical stress

on the pump. Another advantage is linear stopping with this prevent pump damage due to water hammer

Pump Specifications:

Type......BV150 D285 Max. capacity......430 m3 /o'clock

Max. head......24 mwk
Connection partsDN150 (6?)

Aroused your interest? Please feel free to contact us for more information.

Throughput capacity: 430 m3/h Max dirt passage: 80 mm Max. head: 24 MWK Weight: 1640 kg